



Addendum Number 1

Well 3 Decommission Project

Issued February 5, 2020

Addendum Description

The units for the quantity of neat cement required for the project is incorrect. The correct units are cubic feet not cubic yards. The change occurs on page 2 under the **Scope of Services** section heading. The revised text is displayed below.

Scope of Services

This project includes the removal of the existing submersible pump and motor from the well shaft. The contractor will need to secure permits to complete the project from Kane County, and other agencies if necessary. The well must be sealed and abandoned per Kane County regulations, permit requirements and applicable ANSI/AWWA Standards. The job site must be kept secure at all times. The specific well abandonment procedure will be determined by the contractor. We anticipate the items that would need to be completed include removal and disposal of submersible pumping equipment. We also anticipate this work includes encapsulating two unrecoverable submersible wells by setting cement tubing to a depth of 1230 feet and injecting ~~130 cubic yards~~ **cubic feet** of neat cement. The removal of the cement tubing, and backfilling with disinfected pea gravel from 1230 feet to 625 feet, with bentonite from 625 feet to 500 feet, with concrete from 500 feet to 2 feet and the removal of the well casing 2 feet below grade which would be then backfilled with approved fill to original grade. These are approximate depths. The actual depths of each layer of backfill and quantity of each material used as backfill shall be documented and recorded.

Action Required

1. Please sign below acknowledging the change.
2. Return this page with your proposal.

Signature

Date

Printed Name

Title