

Tanner / Remington Outfall Conveyance System Project
Village of North Aurora
ADDENDUM NO. 1
September 27, 2023

This addendum applies to the Village of North Aurora Contract Documents and Project Specifications entitled: "Tanner / Remington Outfall Conveyance System Project" issued for bid on September 19, 2023.

This Addendum forms part of the Contract Documents and modifies the original bidding documents as noted below. Acknowledge receipt of this Addendum on the Bid Form. Bids shall include all items included in this Addendum. **This Addendum shall be stapled to the original Contract Documents which shall be included as part of the "SEALED BID DOCUMENTS."**

Contract Documents

The following revisions/clarifications shall be made part of the Contract Documents, and shall be considered in preparing the proposal:

1. Revisions to the special provision section entitled, "SP-17 STORM SEWERS" located on page 26 of the special provisions are as follows:

- a. The third paragraph which reads, *"All granular materials (CA-6 aggregate) from the trench bottom (4" below the outside bottom of the pipe) to the spring line of the pipe beneath non-pavement areas shall be considered incidental backfill materials and included in the cost of the storm sewer pipe."*

shall be deleted and replaced with the following paragraph, *"All granular materials (CA-7 aggregate) from the trench bottom (4" below the outside bottom of the pipe) to the spring line of the pipe beneath non-pavement areas shall be considered incidental backfill materials and included in the cost of the storm sewer pipe."*

2. Revisions to the special provision section entitled, "SP-25 GRANULAR BACKFILL" located on page 29 of the special provisions are as follows:

- a. The first sentence in the second paragraph which reads, *"All granular materials (CA-6 aggregate) from the trench bottom (4" below the outside bottom of the pipe) to the spring line of the pipe beneath non-pavement areas shall be considered incidental backfill materials and included in the cost of the storm sewer pipe."*

shall be deleted and replaced with the following sentence, *"All granular materials (CA-7 aggregate) from the trench bottom (4" below the outside bottom of the pipe) to the spring line of the pipe beneath non-pavement areas shall be considered incidental backfill materials and included in the cost of the storm sewer pipe."*

END OF ADDENDUM NO. 1
